BILL OF QUANTITIES

Reinforced Concrete Works - Section Summary Extract

Project	Precinct 8 Residential Development, Putrajaya
Subcontractor	Hiform (M) Sdn Bhd
Pricing basis	Remeasurement - estimated quantities at fixed rates
Estimated total	RM12,000,000
Revision	Rev 0

BQ Section Summary

Item	Description	Unit	Estimated Qty	Rate (RM)	Amount (RM)
1.01	Reinforced concrete structural works	m3	10,000	610.00	6,100,000.00
2.01	Formwork and temporary support associated with RC works	m2	50,000	50.00	2,500,000.00
3.01	Reinforcement fixing and related labour	t	2,200	1,000.00	2,200,000.00
4.01	Small plant, tools and ancillary RC works	Item	1	1,200,000.00	1,200,000.00
	Estimated Total				**12,000,000.00**

BQ Note 1 - Measurement

Quantities shown are provisional for pricing purposes. The final subcontract value shall be based on actual quantities measured in accordance with the applicable measurement rules and valued at the fixed rates stated in the Bill of Quantities, subject to properly valued variations.

BQ Note 2 - Scope Boundary

The package covers reinforced concrete works and directly associated labour, materials, temporary support, small plant, equipment and tools required to execute that package. Permanent structural design responsibility is not transferred to Hiform unless expressly instructed and agreed in writing.

BQ Note 3 - Instructions and Variations

Variations must be instructed or confirmed in writing by PBT. Hiform shall notify PBT of any additional cost or time effect within 7 calendar days after receipt of the relevant instruction. Existing BQ rates apply where the varied work is of similar character and executed under similar conditions. Where no suitable rate exists, a reasonable new rate shall be agreed based on demonstrable labour, material, plant and overhead cost where practicable before certification.

BQ Note 4 - Daywork

Daywork applies only where PBT expressly directs daywork in writing and daily records are signed by both parties.

BQ Note 5 - Document Precedence

For commercial scope and pricing, the signed Letter of Award and agreed amendments take precedence, followed by the BQ / pricing schedule, approved drawings and specifications, and Hiform's accepted quotation and clarifications. A specific negotiated exclusion recorded in the Letter of Award prevails over a general lower-precedence requirement.